

UNCLASSIFIED

AD NUMBER

AD499452

LIMITATION CHANGES

TO:

Approved for public release; distribution is unlimited.

FROM:

Distribution authorized to U.S. Gov't. agencies and their contractors;  
Administrative/Operational Use; 28 JAN 1952.  
Other requests shall be referred to Naval Proving Ground, Dahlgren, VA.

AUTHORITY

NSWC ltr dtd 11 Jun 1975

THIS PAGE IS UNCLASSIFIED

**THIS REPORT HAS BEEN DELIMITED  
AND CLEARED FOR PUBLIC RELEASE  
UNDER DOD DIRECTIVE 5200.20 AND  
NO RESTRICTIONS ARE IMPOSED UPON  
ITS USE AND DISCLOSURE.**

**DISTRIBUTION STATEMENT A**

**APPROVED FOR PUBLIC RELEASE;  
DISTRIBUTION UNLIMITED.**

ATI No 204197

ASTIA FILE COPY

UNANNOUNCED

UNCLASSIFIED

AD499452

FILE COPY  
LOAN ONLY

U. S. NAVAL PROVING GROUND  
DAHLGREN, VIRGINIA

REPORT NO. 911

WARHEADS FOR AIR TARGET GUIDED MISSILES  
TESTING OF

GUIDED MISSILE WARHEAD FRAGMENTATION  
TEST OF

35th Partial  
Report

Copy No. 12

Task  
Assignment NPG-Re3f-607-1-52

Classification ~~SECRET~~ L  
SECURITY INFORMATION

UNCLASSIFIED

DDC  
RECEIVED  
MAY 25 1971  
A

AD No.

DDC FILE COPY

UNANNOUNCED

UNCLASSIFIED

NPG REPORT NO. -911

U. S. NAVAL PROVING GROUND  
DAHLGREN, VIRGINIA

10 V. / Philipchuk  
a. n. / Hughes

14  
JFC

9

Thirty-fifth Partial Report.

no. 35, ~~and~~

6

on

Warheads for Air Target Guided Missiles,

Testing of,

-----  
Guided Missile Warhead Fragmentation,

Test of,

DOWNGRADED AT 3 YEAR INTERVALS;  
DECLASSIFIED AFTER 12 YEARS  
DOD DIR 5200.10

DDC  
RECEIVED  
MAY 25 1971  
RECEIVED

16

12 17p.

28 Jan 52

Project No.: NPG-Re3f-607-1-52  
Copy No.: 12  
No. of Pages: 7

Date: JAN 28 1952

SECURITY INFORMATION

UNCLASSIFIED

251 575 ✓

Incc

SECTION 10

DATE SECTION ☐

DATE SECTION ☐

ACKNOWLEDGED ☒

INITIALS

DISTRIBUTION/AVAILABILITY CODES

DATE	TYPE	NO. OF SERIAL
12		

RECEIVED




NP9-45754

12 June 1951

CONFIDENTIAL

Terrier Warhead Type F, BUORD Confidential Sketch 318051.  
Figure 1

UNCLASSIFIED




UNCLASSIFIED

A

CONFIDENTIAL  
SECURITY INFORMATION

Ring for Terrier Warhead Type F, BUORD Confidential Drawing No. 159238. Figure 2




NP9-46653

11 September 1951

CONFIDENTIAL  
SECURITY INFORMATION  
Field set up before firing of Terrier Warhead Type F over NPG Waterpit.

Figure 3





CONFIDENTIAL

NPG REPORT NO. 911

Guided Missile Warhead Fragmentation, Test of

TABLE I

FRAGMENT VELOCITY DATA

35mm Fastax Camera 1

1770 frames per sec.

Rd. 1 - Terrier

Comp. B-1

Total Weight 217.56 lbs.

Filler Weight 114.53 lbs.

Frame in Which  
Hit Occurred

No. Fragments

Velocity (f/s)

17

6

6250

18

45

5900

19

22

5590

20

10

5310

21

2

5060

Median

5860

Average

5760

C

CONFIDENTIAL

NPG REPORT NO. 911

Guided Missile Warhead Fragmentation, Test of

TABLE I (Continued)

35mm Fastax Camera 2 1830 frames per sec.  
Rd. 1 - Terrier Comp. B-1  
Total Weight 217.56 lbs. Filler Weight 114.53 lbs.

<u>Frame in Which Hit Occurred</u>	<u>No. Fragments</u>	<u>Velocity (f/s)</u>
18	12	6100
19	42	5780
20	19	5490
21	9	5230
22	2	4990
Median		5800
Average		5680

CONFIDENTIAL

NPG REPORT NO. 911

Guided Missile Warhead Fragmentation, Test of

TABLE II  
FRAGMENT VELOCITY DATA

35mm Fastax Camera 1	1770 frames per sec.
Rd. 1 - Terrier 3 x 3 Plate	Comp. B-1
Total Weight 217.56 lbs.	Filler Weight 114.53 lbs.

<u>Frame in Which Hit Occurred</u>	<u>No. Fragments</u>	<u>Velocity (f/s)</u>
8	10	6640

Median

Average

CONFIDENTIAL

NPG REPORT NO. 911

Guided Missile Warhead Fragmentation, Test of

TABLE II (Continued)

35mm Fastax Camera 2	1830 frames per sec.	
Rd. 1 - Terrier 3 x 3 Plate	Comp. B-1	
Total Weight 217.56 lbs.	Filler Weight 114.53 lbs.	
Frame in Which <u>Hit Occurred</u>	<u>No. Fragments</u>	<u>Velocity (f/s)</u>
9	10	6100

Median  
Average



NP9-46654

11 September 1951


CONFIDENTIAL

Steel panels after firing of Terrier Warhead Type F. Panels were at  
60 feet from warhead.

SECURITY INFORMATION

Figure 4





NP9-46655

11 September 1951

CONFIDENTIAL  
SECURITY INFORMATION

Beam spray (60°-120°) fragments from Terrier Warhead Type F, Composition B-1 loaded. Fragments were recovered from NPG waterpit.

Figure 5

E

Guided Missile Warhead Fragmentation, Test of

DISTRIBUTION

Bureau of Ordnance:

Ad3	1
Re2	1
Re3	2
Re3f	5

Chief of Ordnance, Department of the Army Attn: ORDTX-AR	2
--	---

Navy Research Section, Library of Congress Washington 25, D. C. (Via BUORD Re3)	2
--	---

Commanding General, Aberdeen Proving Ground, Aberdeen, Maryland Attn: Technical Information Section Development and Proof Services	1
--	---

Commander, Operational Development Force, U. S. Atlantic Fleet, U. S. Naval Base, Norfolk 11, Virginia	1
--	---

Naval Ordnance Laboratory	1
---------------------------	---

Naval Ordnance Laboratory Attn: Explosives Division Attn: Mr. H. W. Semon	1 1
---	--------

Picatinny Arsenal, Dover, N. J. Attn: Technical Division	1
---	---

Solid Propellant Information Agency APL/JHU, Silver Spring, Maryland	1
---	---

APL/JHU, Silver Spring, Md. Attn: Mr. H. S. Morton (Via INSORD, Silver Spring, Md.)	1
---	---

USNOTS, Inyokern, China Lake, Calif.	1
--------------------------------------	---

Guided Missile Warhead Fragmentation, Test of  
-----

DISTRIBUTION (Continued)

Inst. for Cooperative Research  
JHU/1315 St. Paul St.  
Via: (District Chief, Phila. Ord District  
1500 Chestnut St., Phila. 2, Pa.  
Attn: Mr. Edward R. C. Niles) 1

Director, Research and Development Division  
New Mexico Institute of Mining and Technology  
Socorro, New Mexico  
Via: Development Contract Officer  
New Mexico Institute of Mining and  
Technology, Socorro, New Mexico 1

Local:  
OT 1  
OTZ 1  
OT-1 1  
File 1

UNCLASSIFIED

UNCLASSIFIED

UNCLASSIFIED

NPG REPORT NO. 911

Guided Missile Warhead Fragmentation, Test of  
-----

PART A

SYNOPSIS

1. This test was conducted to determine the fragmentation characteristics of the Composition B loaded Terrier Type F guided missile warhead which was modified for production purposes by the addition of four rows of tack weld.
2. The addition of four rows of tack weld to the guided missile warhead Terrier Type F had no adverse effects on its fragmentation characteristics.

UNCLASSIFIED

~~CONFIDENTIAL~~

Guided Missile Warhead Fragmentation, Test of

UNCLASSIFIED

TABLE OF CONTENTS

	<u>Page</u>
SYNOPSIS . . . . .	1
TABLE OF CONTENTS... . . . .	2
AUTHORITY. . . . .	3
REFERENCES . . . . .	3
BACKGROUND . . . . .	3
OBJECT OF TEST . . . . .	3
PERIOD OF TEST . . . . .	3
REPRESENTATIVES PRESENT. . . . .	4
DESCRIPTION OF ITEM UNDER TEST . . . . .	4
PROCEDURE. . . . .	5
RESULTS AND DISCUSSION . . . . .	5
CONCLUSIONS. . . . .	6
APPENDIX A - WARHEAD DRAWING, PHOTOGRAPHS. . . .	FIGURES 1-2 (Incl)
APPENDIX B - FIELD SET UP, PHOTOGRAPH. . . . .	FIGURE 3
APPENDIX C - FRAGMENT VELOCITY DATA. . . . .	TABLE I 1-2 (Incl) TABLE II 1-2 (Incl)
APPENDIX D - STEEL PANELS AFTER FIRING . . . . .	FIGURE 4
APPENDIX E - MASS DISTRIBUTION, PHOTOGRAPH . . .	FIGURE 5
APPENDIX F - DISTRIBUTION. . . . .	1-2 (Incl)

~~CONFIDENTIAL~~

UNCLASSIFIED



Guided Missile Warhead Fragmentation, Test of  
-----PART BINTRODUCTION

## 1. AUTHORITY:

This test was authorized by reference (a) and conducted under Task Assignment NPG-Re3f-607-1-52, (reference (b)).

## 2. REFERENCES:

- a. NOL Conf ltr NP/NOL/X11(259) WG:HWS:br Ser 01536 of 30 Aug 1951 to NAVPROV
- b. BUORD Conf ltr NP9 Re3f-EJHL:edb Ser 25777 of 18 Sep 1951 to NAVPROV
- c. NPG Conf Report No. 889 of 15 Dec 1951
- d. NPG Conf Report No. 203 of 25 Jan 1949

## 3. BACKGROUND:

a. Reference (b) authorized the Naval Proving Ground to work directly with the Naval Ordnance Laboratory in the development and fragmentation tests of guided missile warheads.

b. The standard construction and fragment characteristics of the Terrier Type F warhead were reported in reference (c). The standard construction had to be modified for production manufacturing by tack welding the rings together in four locations in order to facilitate the ring brazing. The fragmentation results of this modified Terrier Type F warhead are reported herein.

4. OBJECT OF **TEST**:

This test was conducted to determine the fragmentation characteristics of the Composition B loaded Terrier Type F guided missile warhead which was modified for production purposes by the addition of four rows of tack weld.

5. PERIOD OF **TEST**:

- |                                     |             |
|-------------------------------------|-------------|
| a. Date of Project Letter           | 30 Aug 1951 |
| b. Date Necessary Material Received | 6 Aug 1951  |
| c. Date Commenced Test              | 11 Sep 1951 |
| d. Test Completed                   | 11 Sep 1951 |

Guided Missile Warhead Fragmentation, Test of  
-----

## 6. REPRESENTATIVES PRESENT:

This test was witnessed by Mr. L. E. Hightower and Mr. T. C. McGreen representing the Naval Ordnance Laboratory.

PART CDETAILS OF TEST

## 7. DESCRIPTION OF ITEM UNDER TEST:

a. Terrier Warhead Type F, Serial No. 34; one round constructed according to Bureau of Ordnance Conf Sk 318051, Figure 1, Appendix (A), 21"835 in length, tapered from 10"412 O.D. at the nose to 13"500 O.D. at the base, and "409 wall thickness. The warhead contained a 1"9 diameter central conduit tube and the outer shell consisted of 54 notched rings which were copper hydrogen brazed together.

b. The rings were formed from notched wire. For rings 1 through 12, the notches were spaced "718 ± ".025 on centers entirely around each ring. For rings 13 through 54, the notches were spaced "390 ± ".025 on centers entirely around each ring. The rings 1 through 12 were designed to produce 536 fragments weighing approximately 13.3 grams each and rings 13 through 54 were designed to produce 4056 fragments weighing approximately 7.0 grams each. A sketch of ring details is shown in Figure 2, Appendix (A).

Each ring was "375 thick and had a notch depth of "218. Four rows of tack weld held the rings together during brazing. The warhead was loaded with Composition B-1 at Naval Mine Depot Yorktown, Virginia.

The weights are as follows:

<u>Rd.</u> <u>No.</u>	<u>Empty Wt.</u> <u>(lbs)</u>	<u>Hot melt.</u> <u>(lbs)</u>	<u>*Filler Wt.</u> <u>(lbs)</u>	<u>Complete Wt.</u> <u>(lbs)</u>
1	100.00	3.03	114.53	217.56

\*Composition B-1 at 1.66 density.

Guided Missile Warhead Fragmentation, Test of  
-----

## 8. PROCEDURE:

a. The mass distribution collection was conducted by the general method described in reference (d). The warhead was placed horizontally over a water pit so that 1/6 of the beam spray ( $60^\circ$  -  $120^\circ$ ) fragments would be recovered in the water pit. The white stripe which was painted over one of the four welds was on the bottom side of the warhead as it hung in the horizontal position. A photograph of the field set up before firing is shown in Figure 3, Appendix (B).

b. Fragment velocities were measured by the usual photographic technique. Mean velocities of beam spray fragments were obtained for 30' and 60' of fragment travel from the warhead. Steel panels 20' high and 6' wide were placed in the beam spray at 60' from the warhead. The width of the panels covered  $23^\circ$  of the beam spray (from  $78\frac{1}{2}^\circ$  to  $101\frac{1}{2}^\circ$ ) at the 60' radius, Figure 4, Appendix (D). In addition,  $\frac{3}{8}$ " mild steel panels 3' high and 3' wide were placed in the beam spray at 30' from the warhead. The width of these panels covered  $6^\circ$  of the beam spray (from  $87^\circ$  to  $93^\circ$ ).

c. Initiation was accomplished by using a 167 gram tetryl booster, 1.423 diameter by 4.50 long, and a special engineers blasting cap. The booster was placed in the central tube with its front end at  $8\frac{7}{8}$ " from the extreme front end of the warhead.

## 9. RESULTS AND DISCUSSION:

a. A total of 510 fragments of approximately design size for rings 13 through 54 (465 weighing between 5 and 10 grams, 45 weighing between  $2\frac{1}{2}$  and 5 grams) and a total of 94 fragments of approximately design size for rings 1 through 12 (weighing between 10 and 20 grams) were recovered in the water pit. Since these figures represent 1/6 of the total fragments in the beam spray, there should be 3060 fragments weighing between  $2\frac{1}{2}$  and 10 grams and 564 fragments weighing between 10 and 20 grams in the total beam spray ( $60^\circ$  to  $120^\circ$  measured from the nose relative to the longitudinal axis of the warhead). The fragments collected in the water pit are shown in Figure 5, Appendix (E).

b. The mean beam spray fragment velocities for the first 30' and 60' of travel are tabulated in Tables I and II, Appendix (C). The median fragment velocity obtained when viewing the 60' radius panels was 5830 ft./sec., with the fastest fragments having a mean velocity of 6250 ft./sec.

Guided Missile Warhead Fragmentation, Test of

c. The 20' high steel panels at the 60' radius were placed at various polar angle zones and had the following numbers of fragment hits:

<u>Panel Thickness (inches)</u>	<u>Zone</u>	<u>No. Fragment Hits</u>	<u>No. Complete Penetrations</u>	<u>No. Incomplete Penetrations</u>
.125	78-1/2°-84-1/4°	36	36	0
.485	84-1/4°-90°	36	32	4
.493	90°-95-3/4°	49	41	8
.610	95-3/4°-101-1/2°	27	8	19

A photograph of the steel panels after firing is shown in Figure 4, Appendix (D).

PART D

CONCLUSIONS

10. It is concluded that:

The addition of four rows of tack weld to the guided missile warhead Terrier Type F had no adverse effects on its fragmentation characteristics.

Guided Missile Warhead Fragmentation, Test of

UNCLASSIFIED

The tests upon which this report is based were conducted by:

V. PHILIPCHUK, Fragmentation Battery Officer,  
Fragmentation Division,  
Terminal Ballistics Department

This report was prepared by:

V. PHILIPCHUK, Fragmentation Battery Officer,  
Fragmentation Division,  
Terminal Ballistics Department

A. N. HUGHES, Lieutenant, USN, Fragmentation Firing Officer,  
Terminal Ballistics Department

This report was reviewed by:

R. H. LYDDANE, Director of Research,  
Terminal Ballistics Department

W. B. ROBERTSON, Lieutenant Commander, USN,  
Terminal Ballistics Batteries Officer  
Terminal Ballistics Department

R. T. RUBLE, Lieutenant Commander, USN,  
Terminal Ballistics Officer  
Terminal Ballistics Department

C. C. BRAMBLE, Director of Research,  
Ordnance Group

APPROVED: IRVING T. DUKE  
Rear Admiral, USN  
Commander, Naval Proving Ground

*C. T. Mauro*  
C. T. MAURO  
Captain, USN  
Ordnance Officer  
By direction

UNCLASSIFIED



AD No.

Classification:

C-7388

STI-ATI No. 204 197

O. A. H.P.O.

O. A. No. H.P.O. # 911

Title GUIDED MISSILE WARHEAD FRAGMENTATION

Author(s) V. PHILIPCHUK AND A.B. HUGHES

Date PARTIAL REPT. 35 on WARHEADS FOR AIR TARGET  
GUIDED MISSILES 28 Jan 62

P. A.

P. A. No.

DSC Form 49 (Jan 54)